(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, sump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary, provide for the same by insurance at the proper time.

(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. "Chamundi" Brand cement alone to be used.

Abstract estimate for constructing a bridge at "4—6" of Holalkere-Huliyar Road.

Serial No.	Details of work	Unit	Quantity	Rate
				Rs. a. p.
1	E. W. excavation in wet sand and soft rock	C.yds.	174	0 5 0
2	Stone jelly concrete in mortar	C.ft.	527	0 4 0
3	Size stone in mortar	,,	5,310	0 4 6
4	Reinforced concrete 1 : 2 : 4 with suitable reinforcement ..	,,	531	1 12 0
5	Cement concrete 1 : 2 : 4	C.ft.	213	0 12 0
6	Rough stone work	C.yds.	89	1 8 0
7	Cement pointing	Sqrs.	15.21	3 8 0
8	Hand railings 2 lines with angle iron pieces and 1½" galvanised iron pipes fixing in concrete with required anchoring bolts and nuts	R.ft.	136	1 14 0
9	Earthwork banking with good earth both sides of the bridge ..	C.yds.	867	0 3 0
10	Metalling and gravelling road-way with soling and 3" broken metal :—			
	(*a*) Collecting and stacking the metal including lead ..	C.yds.		
	(*b*) Spreading and consolidating the metal	Sq.yd.		
	(*c*) Collecting and stacking gravel including lead ..	C.yd.		
	(*d*) Spreading and consolidating gravel	Sq.yd.		
	(*e*) Collecting and spreading sand	C.yd.		
	(*f*) Collecting, spreading and consolidating soling metal	C.yd.		
11	Deviating road—during execution barricading, providing danger light and watch :—			
	(*a*) Earthwork excavation and filling in pits	C.yds.		
	(*b*) Earthwork banking	,,		
	(*c*) Removing jungle	Sq.yds.		
	(*d*) Providing danger light	Month		
	(*e*) Barricading the road	No.		

S. RAMASWAMY,
Executive Engineer.

MEDICAL DEPARTMENT

CIVIL HOSPITAL, KOLAR GOLD FIELDS, ROBERTSONPET.

Abstract Notification.

Sealed tenders in triplicate will be received at the Office of the District Medical Officer, Kolar Gold Fields, Robertsonpet, on 22nd February 1939 at 11 A.M., for the supply of bedding and clothing for the Civil Hospital, Robertsonpet, for the year 1938-39. For details *vide* page 165, Part VI of the *Mysore Gazette*, dated 19th January 1939.

C. NARAYANA RAO,
District Medical Officer.